BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK: Construction of RCC Drain 17th B Cross Near Geetha school in Prashanth nagara in ward no 13 SSD

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	225.00	200.00	Two Hundred Only
2	Removing BS -Slab drain and Stacking	Sqm	337.50	100.00	One Hundred Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.				
	A) Using Available Course Aggregates	Cum	29.78	4500.00	Four Thousand Five Hundred only
	B) Remaining Balance Quantity	Cum	7.72	6000.00	Six Thousand Only
4	Providing and Laying in position reinforced cement concrete of design mix M20 with OPC cement @ 300Kgs with 20mm and down size graded granite metal course aggregate @ 0.69cum and fine aggregate @ 0.43cum, with superplastisiser @ 3ltr confirming to IS 9103-1999 Reaffirming 2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground level for roof slab, stairecase, lintels, retaining wall , return wall, wall (any thickness) including attahed plasters, column , piers, abutmentspillers, posts, struts, buttresses, string or laceing courses, parapets, coping, bed blocks, anchor hooks plain window ,cill, fillets, etc.., including cost of all materials, Labours, HOM of Machineries, curing complete as per specification	Cum	93.75	6100.00	Six Thousand One Hundred only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications,	Sqm	900.00	333.00	Three Hundred Thirty Three Only
6	Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. for TMT Bars Fe 500 Specification	Tone	5.63	65000.00	Sixty-Five Thousand Only

Signature of the Contractor

EXECUTIVE ENGINEER

Scanned by CamScanner